
MODEL 209.3## 1#

with CODE (494) USA version with CODE (806) Model year 2006


MODEL 209.3## 1#


with CODE (494) USA version with CODE (807) Model year 2007 with CODE (810) Sound system

- 1 SDAR control unit
- 2 SDAR antenna
- 12 SDAR bracket



P82.60-5758-06





P82.60-5759-08

Illustrated on Model 203.0

41 Sound amplifier bracket

42 Sheet metal nut

43 Bolt

44 Sound amplifier connector


45 Fiber optic cable connector

46 Nut

A2/13 Sound amplifier

| X         | Removal  |   |                    |
|-----------|--|---|--------------------|
| (3)       | Notes on avoiding damage to electronic components due to electrostatic discharge   |   | AH54.00-P-0001-01A |
| ⚠ Danger! | Risk of explosion caused by oxyhydrogen gas. Risk of poisoning and caustic burns caused by swallowing battery acid. Risk of injury caused by burns to skin and eyes from battery acid or when handling damaged lead-acid batteries | No fire, sparks, open flames or smoking.<br>Wear acid-resistant gloves, clothing and<br>glasses. Only pour battery acid into suitable<br>and appropriately marked containers. | AS54.10-Z-0001-01A |
| 1<br>⊯≆AR | Disconnect battery ground cable  |   | AR54.10-P-0003Q    |

| (1)           | Notes on battery   |   | AH54.10-P-0001-01A                   |
|---------------|--|---|--------------------------------------|
| i             | Notes on AGM battery   |   | AH54.10-P-0002-01A                   |
| <u>*</u><br>2 | Remove coverings in trunk  |   | 74104.101 0002 0174                  |
| -<br>FAR      | nemove coverings in trunk  |   | AR68.30-P-4600PB                     |
| ₃<br>⊯FAR     | Remove paneling from trunk lid   |   | AR68.30-P-8150Q                      |
| 4             | Remove rear SAM control unit with fuse and relay box   | i Do not disconnect electrical connectors.  |                                      |
| ≆ AR          | ,  |   | AR54.21-P-1259Q                      |
| 5             | Remove sheet metal nut (42) and bolt (43), disconnect sound amplifier connector (44) and fiber optic cable connector (45), remove nuts (46), remove sound amplifier (A2/13) and sound amplifier bracket (41) | i The sound amplifier bracket (41) is no longer required. i On vehicles with model year 2006 (code 806) without sound system (code 810), a styrofoam block is fitted on the sound amplifier bracket (41) in place of the sound amplifier (A2/13). |                                      |
| <b>()</b>     | Notes on fiber optic cable   | ,   | AH82.70-P-0001-02A                   |
| X             | Install  |   |                                      |
| ⚠ Danger!     | Risk of explosion and poisoning caused<br>by solvent vapors and gasses. Risk of<br>injury to skin and eyes when working with<br>anticorrosion agents   | Never spray anticorrosion agents on flames or glowing hot objects and keep them well away from all potential sources of ignition. Use them only in well-ventilated rooms; wear respiratory protection.  | AS97.00-Z-0001-01A                   |
| 6             | Retrofit satellite radio antenna   |   | AZ82.60-P-0006-02P                   |
|               |  | Zinc dust paint suitable for spot welding   | *BR00.45-Z-1001-07A                  |
| 7             | Retrofit antenna line  | i Antenna line for SDAR.  | AZ82.70-P-0002-01P                   |
| 3             | Retrofit wiring harness.   | i Wiring harness for SDAR.  |                                      |
|               |  | Vehicles with sound system (code 810).  | AZ82.70-P-0001-04P                   |
|               |  | Vehicles with model year 2006 (code 806) without sound system (code 810).   | AZ82.70-P-0001-04PA<br>*220589029900 |
| 9             | Retrofit MOST fiber optic cable wiring harness   | i MOST fiber optic cable wiring harness for SDAR.   |                                      |
|               |  | Vehicles with sound system (code 810).  | AZ82.60-P-0006-03P                   |
|               |  | Vehicles with model year 2006 (code 806) without sound system (code 810).   | AZ82.60-P-0006-03PA                  |
| 10            | Retrofit satellite radio control unit  |   | AZ82.60-P-0006-01P                   |
| 1             | Install in the reverse order   | i Steps 4 up to 1.  |                                      |
| 12            | Perform retrofit variant coding  | i Perform variant coding using STAR DIAGNOSIS to activate the satellite radio (SDAR) functions. After completing variant coding, perform a quick test and delete the fault memory.  |                                      |
| 13            | Carry out function check of satellite radio (SDAR).  |   |                                      |
| 14            | Add special equipment to the vehicle data card and to the online vehicle data card   | i Enter SIRIUS satellite radio (code 536).  |                                      |



Wiring harness repair kit

## Repair materials

| Number             | Designation                               | Order number    |
|--------------------|---|-----------------|
| BR00.45-Z-1001-07A | Zinc dust paint suitable for spot welding | A 000 986 34 42 |

## Parts ordering notes

| Part no.     | Designation       | Quantity |
|--------------|-------------------|----------|
| B6 783 00 73 | SDAR assembly kit | 1        |

| B6 783 01 16 | SDAR wiring harness                | 1           |
|--------------|------------------------------------|-------------|
| B6 783 01 12 | SDAR-MOST wiring harness           | 1           |
| B6 783 00 60 | SDAR receiver                      | 1           |
| B6 783 00 93 | SDAR antenna line                  | 1           |
| B6 783 00 80 | SDAR antenna, black 9040           | As required |
| B6 783 00 81 | SDAR antenna, cubanite silver 9723 | As required |
| B6 783 00 82 | SDAR antenna, iridium silver 9775  | As required |
| B6 783 00 83 | SDAR antenna, alabaster white 9960 | As required |
| B6 783 00 84 | SDAR antenna, primed               | As required |