




## MODEL 209.4

- 1 Connector  
 2 Bolt  
 3 Flap  
 S84/18 Soft top limit switch in catch position



P77.33-2101-06

	Remove/install		
1	Completely open soft top		
2	Remove paneling from windshield at top		AR68.30-P-4250QA
3	Disconnect connector (1) from soft top limit switch in catch position (S84/18)		
4	Remove screw (2)		
5	Press flap (3) from top to bottom	 Press flap (3) down to remove soft top limit switch in catch position (S84/18)	
6	Remove soft top limit switch in catch position (S84/18)		
7	Install in the reverse order		